KOLAR DIVISION.

Dated 24th April 1910.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 3-30 P. M. 14th May 1910, for restoring the Mamallapalli Anikat and Channel in the Srinivaspur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include royalty on stones, etc., removed from the Government lands, to be paid to the Government.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory notes as earnest money and be superscribed "Tender for restoring Mamallapalli Anikat and Channel in the Srinivaspur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

	Items of work	Per	Quantity
Tie Bank ...	Earthwork	C. yd.	206
	Rough stone work, new	"	24
	Turfing	S. yd.	75
Anikat ...	Excavating sand and boulders mixed	"	665
	Benching and blasting rock	Lump	sum Rs.
	Surki concrete filling for foundation	C. ft.	1,326
	Burnt brick in surki-mortar	"	1,118
	Burnt stone in chunam	"	4,682
	Burnt stone slabs nicely dressed	S. ft.	996
	Plastering with surki chunam	Sqr.	6·44
	Pointing with do	"	12·29
	Rough stone work new	C. yd.	45
	do old	"	495
	Grouting with concrete and pointing	Sqr.	2·70
	Bailing water	Lump	sum Rs.
	Levelling with concrete at fissures between rocks in 58 ft. section	"	"
	Lowering rock wherever necessary	"	"
Head Sluice ...	Excavating soft rock, benching and blasting rock ...	"	"
	Laying concrete	C. ft.	47
	Burnt stone in chunam	"	1,065
	Cut stone caps	Lump	sum Rs.
	Burnt stone slabs including dressing	S. ft.	240
	Grooving and fixing sill slabs, guide slabs	Lump	sum Rs.
	Pointing with surki chunam	Sqr.	7·79
	Preparing and fixing teakwood shutters with gear rod, etc., complete	Lump	sum Rs.
	Wooden teak beam	C. ft.	12
Channel ...	Earthwork	C. yd.	29·824
	Turfing	S. yd.	21,560
	Mile stone	No.	3
	Bank grade stones	"	38
	Bed grade stones	"	38
	Constructing madaboys as per estimate	Each	6
	Do cattle bridges as per estimate	"	2
	Do relieving weirs at required places ...	Lump	sum Rs.

B. B. GARUDACHARYA, *Executive Engineer.*